

BID SPECIFICATIONS REPAVE/OVERLAY

SPECIFICATIONS:

Repave/overlay roadway with 2" overlay with binder for leveling, tack and E-Surface. The shoulders need to be clipped and swept. Striping will need to be included on noted roads. Driveway aprons need to be paved for sufficient use of landowner and prevent damage to street paving. The bid should be submitted by cost per street allowing for the option to pick streets as budget allows. Work intended to be completed and paid prior to June 30, 2025.

The roads to be paved are as follows:

Mirandy Rd from E Main St to Hwy 111 N grind and pave with striping

W Wall St from W Main St to 5th Ave

Quinland Lake Rd in marked locations **with striping replaced as required**; grind and pave; site visit can be arranged.

***Section 1 - Single lane approximate length is 390 ft marked in white paint**

***Section 2 - Single lane approximate length is 149 ft marked in white paint**

4th Ave in marked location at intersection **with striping as required**; grind and pave; site visit.

***Single lane approximate length 100 ft marked in white paint between Circle Dr intersections**

Swift St

Markwater St

Timber View Lane from Mirandy Rd to intersection marked at Aspen Trail

Aspen Trail at top of hill as marked 2" overlay

UTILITIES

Utility owners will adjust all sewer manhole castings, water and gas valve boxes and drainage grates within the pavement to proposed grade prior to paving.

The contractor will provide all necessary protective measures to safeguard existing utilities from damage during the construction of this project. In the event that special equipment is required to work over and around the utilities, the contractor will be required to furnish such equipment.

The contractor shall notify each individual utility owner of his plans of operation in the area of utilities prior to commencing work. The contractor shall contact the utility owners and request them to properly locate their respective utility on the ground. This notification shall be given at least three (3) business days prior to commencement of operations around the utility.

Underground utilities can be located by all The Tennessee One Call System at 811.

MISCELLANEOUS

Prior to construction, the contractor shall be responsible for insuring that all required federal, state and local permits and approvals have been obtained. No construction or fabrications shall begin until the contractor has received and thoroughly reviewed all plans and other documents approved by all applicable permitting authorities.

Any property damage caused by the contractor or his operations shall be corrected and/or restored to the satisfaction of the property owner and the engineer at no additional cost to the owner.

Street signs, mailboxes, etc. shall be relocated as necessary by the contractor. All cost to be included in other items of work.

The contractor shall take the necessary measures to provide for the safety and convenience of the general public and the residents along the proposed construction route while work is in progress.

Notice to Bidders

The City of Algood will receive sealed Bids until Thursday, May 1, 2025, for street paving. No faxed bids or e-mailed bids will be accepted. No bids will be accepted after 10:00 a.m. (CST). Bid opening will be Thursday, May 1, 2025 at 10:00 a.m. (CST) at Algood City Hall.

Specifications may be obtained by contacting the City of Algood, at [931-537-9545](tel:931-537-9545), email to keith.morrison@algoodtn.gov, or online at www.algood-tn.com.

All bids must be mailed or delivered to the City of Algood, ATTN: Street Paving Bid 2025, 215 W Main Street, Algood, TN 38506. All envelopes must be marked "Street Paving 2025".

City of Algood reserves the right to reject any or all bids.

Keith Morrison,
City Administrator